



**CENTRE FOR RESEARCH IN RURAL &
INDUSTRIAL DEVELOPMENT**
SECTOR 19A, MADHYA MARG, CHANDIGARH 160 019

MAINTENANCE WORK AT CRRID

The Centre for Research in Rural and Industrial Development (CRRID), Plot 2-A, Sector 19-A, Madhya Marg, Chandigarh – 160019, invites the item bids for following work.

Sr. No	Detail of Maintenance Work of Shed Over Library Building
1.	Dismantling of the existing broken PVC sheet shed and dump the Malba out of the premises.
2.	P/F of brick work with plaster 4.5" thick
3.	P/Fixing of aluminium partition with clear glass 10 mm thick toughened complete with rubber and groove filling etc.
4.	P/Fixing of aluminium partition with ACP sheet 4mm thick off-white colour complete with rubber and groove filling etc.
5.	P/Fixing of 12mm thick toughened glass on top of aluminium partition walls in slant level, glass clear colour, grooves and gaps fill with silicon adhesive, rubbers etc.
6.	P/Fixing of D-seal weather proof for covering of slope groove and sides of all edges of glass for safety glass corners breakage
7.	Providing and applying two coats of white cement-based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get an even and smooth finish including cost and carriages of all material, labour charges, scaffolding, sundries, etc. Complete
8.	Wall painting on a cement plaster surface with acrylic emulsion paint of approved brand and manufacture to give an even shade. Two or more coats as required.
9.	Applying priming coat: with ready mixed red oxide zinc chromate primer of approved sqm 15 6 22 brand and manufacture on steel galvanised iron/steel works
10.	Providing and fixing glass panes with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 5 mm (weight sqm 168 754 922 not less than 12.5kg/sqm

Interested bidders may make an on-site visit to gather first-hand information and assess the nature of activities that are required for the completion of these works. Rates per sq. feet (in Rs) may be quoted for carrying out 1 to 10 activities, as mentioned above.

The quotations may be sent in sealed envelope to Secretary & Establishment Officer (Acting), CRRID, by 5.00 pm, March 26, 2024. The undersigned has right to extend or cancel the bids without declaring any reason thereof.

S&EO, CRRID
2-A, Sector 19-A
Madhya Marg
Chandigarh 160019



**CENTRE FOR RESEARCH IN RURAL &
INDUSTRIAL DEVELOPMENT**
SECTOR 19A, MADHYA MARG, CHANDIGARH 160 019

MAINTENANCE WORK AT CRRID

The Centre for Research in Rural and Industrial Development (CRRID), Plot 2-A, Sector 19-A, Madhya Marg, Chandigarh – 160019, invites the item bids for following work.

Sr. No	Detail of Maintenance Work: Removal of CV Pipe from Library area and placing UPVC Pipe to stop Leakage/Seepage
1.	Dismantling cement concrete manually by mechanical means including disposal of material within 50 meters lead. Nominal concrete 4:4.5:3 or richer mix
2.	Dismantling old cracked C.I Pipes including excavation and refilling trenches after taking out the pipes, breaking lead caulked joints, melting of lead and making into blocks, including stacking of pipes on site lead up to 50 meters
3.	Earth work in excavation by mechanical means (Hydraulic excavation) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead up to 50 m and lift up to 1.5 m.
4.	Providing and laying in position cement of specified grade excluding the cost of centering and shuttering- all work below plinth level and up to floor IV level: 1:1.5:3 (1 cement: 1.5 coarse sand (zone-III): 3 cum graded stone aggregate 20 mm nominal size
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering = All work below plinth level and up to floor IV level: 1:4:8 (1 cement: 4 coarse sand 9zone III): 8 graded stone aggregate 40 mm nominal size) below pipe and top surface
6.	Constructing brick masonry road sully chamber 110 x 50 x77.5 cm with bricks in cement mortar 1:4 (1 cement: 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame and vertical grating complete as per standard design. With common burnt clay non-modular bricks of class designation each 7.5-man hole
7.	Providing and fixing in position single socket SWR UPVC soil waste or antisiphomage pipes as per IS13592 of E.D.C. manufacture or of any other reputed firm including cutting, pointing, wastage, but excluding cost of jointing 160 mm o/d SWR UPVC pipe lines laid complete

Interested bidders may make an on-site visit to gather first-hand information and assess the nature of activities that are required for the completion of these works. Rates per sq. feet (in Rs) may be quoted for carrying out 1 to 10 activities, as mentioned above.

The quotations may be sent in sealed envelope to Secretary & Establishment Officer (Acting), CRRID, by 5.00 pm, March 26, 2024. The undersigned has right to extend or cancel the bids without declaring any reason thereof.

S&EO, CRRID
2-A, Sector 19-A
Madhya Marg
Chandigarh 160019